
Building Data Summary			
Project ID:	******		
Location:	******		
Scope of Work:	Flooring		
Date:	******		

Item #	Ref. Sheet #	Item Description	Unit	Quantity	Wastage	Quantity with Wastage
		DIVISION 2- Demolition				
	T	Demolition Demolition			Ī	T
1		Remove Flooring	SF	21782	0%	21782
2		Remove Wall Base	LF	2886	0%	2886
3	D101A-	Remove Transition Strip	LF	460	0%	460
	D103B	Alternate				
4		Remove Flooring	SF	7180	0%	7180
5		Remove Wall Base	LF	837	0%	837
		dil 14º			-	
		DIVISION 9- Finishes				
		Flooring	Î			
6		Existing Flooring To Be Cleaned	SF	12604	5%	13234
7		Re-Grout Existing Floor Tile	SF	2622	5%	2753
8		CPT1 Carpet Tile Size: 6' ROLL Manuf: TARKETT Style: POWERBOND CUSHION Color: COROLLARY 11577 VARIFORM 39402	SF	21851	5%	22944
		Wall Base				
9		Wall Base Size: 4" COVE Manuf: TARKETT-JOHNSONITE,ROPPE Style: RUBBER BASE Color: 63 BURNT UMBER	LF	2885	5%	3029


Item #	Ref. Sheet #	Item Description	Unit	Quantity	Wastage	Quantity wit Wastage
	7	Transition Strip]	1
		TS1				
	A101A-	Transition Strip				
10	A103B	Manuf: TARKETT-JOHNSONITE,ROPPE	LF	460	5%	483
		Style: ADAPTER,REDUCER				
		Color: 63 BURNET UMBER				
		Alternate				
		Flooring				
11		CPT1				
		Carpet Tile				
		Size: 6' ROLL	SF	6405	5%	6725
		Manuf: TARKETT	31			
		Style: POWERBOND CUSHION				
		Carpet Tile Size: 6' ROLL Manuf: TARKETT Style: POWERBOND CUSHION Color: COROLLARY 11577 VARIFORM 39402				
		Wall Base				
		B1		721	5%	757
		Wall Base				
12		Size: 4" COVE	LF			
12		Manuf: TARKETT-JOHNSONITE, ROPPE				
		Style: RUBBER BASE				
		Color: 63 BURNT UMBER				

DEMOLITION NOTE LEGEND DEMO-I REMOVE EXISTING FLOORING MATERIALS, WALL BASE, AND TRANSITIONS IN THEIR ENTIRETY TO EXISTING SUBTRATE, PREP SUBSTRATE FOR NEW FLOORING. DEMO-2 ADD ALTERNATE #1: REPLACE CARPETING IN OFFICE AREAS, MEDIA CENTER/COMPUTER, & CORRIDORS

DEMOLITION SYMBOL LEGEND			
EXISTING TO BE DEMOLISHED	[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[[
AREA OUT OF SCOPE			
AREA OF EXISTING CONSTRUCTION TO BE DEMOLISHED			



KEY PLAN





CESAR E CHA ELEMENTARY SCHOOL RENC 1205 César E. Chávez Ave. SW. Grand Rabids

25.102

FIRST FLOOR-PART A DEMOLITION PLAN

D101a



CORNERSTONE
ARCHITECTS
1225. Union, 51e. 202
440 Bidge 51. NW
10rowne 10f. MI
23 1947.24776
Www.cornestone arch.com

GRPS my choice

GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION

 Date
 Issued For

 02.14.2025
 SD PROGRESS


 02.28.2025
 SCHEMATIC DESIGN

 03.18.2025
 BIDS & PERMITS


ROJECT NO: 25.102

FIRST FLOOR-PART B DEMOLITION PLAN


D101b







KEY PLAN





GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION

 Date
 Issued For

 02.14.2025
 SD PROGRESS

 02.28.2025
 SCHEMATIC DESIGN

 03.18.2025
 BIDS & PERMITS

25.102

SECOND FLOOR-PART A DEMOLITION PLAN

D102a



CORNERSTONE ARCHITECTS
122.6. Injen. 34e. 200 440 Bridge 31. NW. Injension 34e. 200 440 Bridge 31. NW. Injension 34e. 2017 p. 416.774.0100 p. NWW. cornentone arch.com

Size Paper Paper Salask

GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION

 Date
 Issued For

 02.14.2025
 SD PROGRESS

 02.28.2025
 SCHEMATIC DESIGN

 03.18.2025
 BIDS & PERMITS


: T. Nem
A. Dano
AFTS: A. Dano

25.102

SECOND FLOOR-PART B DEMOLITION PLAN

D102b

DEMOLITION SYMBOL LEGEND			
EXISTING TO BE DEMOLISHED	[======]		
AREA OUT OF SCOPE			
AREA OF EXISTING CONSTRUCTION TO BE DEMOLISHED			



KEY PLAN



CORNERSTONE
ARCHITECTS
ARCHITECTS
1725. Union, 58e. 200 440 Bidgle 51. HW
Tovene City, MI
23.1947.2177 a Grand Repols, MI
23.1947.2177 b Grand Repols, MI
23.1

VEZ WATION MI 49503

GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION


: T. Nem


25.102

THIRD FLOOR-PART A DEMOLITION PLAN


D103a

DEMOLITION NOTE LEGEND DEMO-1 REMOVE EXISTING FLOORING MATERIALS, WALL BASE, AND TRANSITIONS IN THEIR ENTIRETY TO EXISTING SUBTRATE FOR NEW FLOORING. DEMO-2 ADD ALTERNATE #1: REPLACE CARPETING IN OFFICE AREAS, MEDIA CENTER/COMPUTER, & CORRIDORS











THIRD FLOOR - PART B DEMOLITION PLAN
SCALE: 1/8" = 1'-0"

CORNERSTONE
ARCHITECTS
125 I, Urlon, 5to, 200
140 Bridge 51, NW
100vens Chy, Mil
23,1942,177 del.6774,010 p
www.comestone-arch.com

EZ ATION


CESAR E CHAVI
LEMENTARY SCHOOL RENOVA

Date Issued For U2.14.2025 SD PROGRESS 02.28.2025 SCHEMATIC DESIGN 03.18.2025 BIDS & PERMITS

25.102

THIRD FLOOR-PART B DEMOLITION PLAN

D103b



CORNERSTONE
ARCHITECTS
125 Linion, 5to, 200
125 Linion, 5to, 200
123,1942/177
Www.cornestone-arch.com

GESAR E CHAVEZ
ELEMENTARY SCHOOL RENOVATION
1205 César E. Châvez Ave. SW. Grand Rapids. MI 49503

 Date
 Issued For

 02.14.2025
 SD PROGRESS

 02.28.2025
 SCHEMATIC DESIGN


 03.18.2025
 BIDS & PERMITS

T. Nemit

25.102

FIRST FLOOR PLAN - PART A

A101a



GENERAL FINISH NOTES

1. PROJECT CLEAN UP SHALL INCLUDE A "VACUUM CLEAN" INTERIOR SPACE WITH RESTORATION TO "LIKE NEW" CONDITIONS OF ALL DAMAGED SURFACES AND ITEMS.

 $2.\mbox{ALL}$ FASTENINGS AND ATTACHMENTS OF LIKE AND DIFFERENT MATERIALS SHALL BE FULLY CONCEALED FROM VIEW.

3.ALL MATERIAL FINISH SELECTIONS (COLORS, MANUFACTURERS, PATTERNS, ETC.) TO BE DETERMINED BY ARCHITECT AND APPROVED BY BUILDING OWNER. SAMPLES OF ALL FINISHES SHALL BE SUBMITTED TO THE ARCHITECT OR APPROVAL PRIOR TO ORDERING AND INSTALLING. SHOP DRAWINGS SHALL INCLUDE LOCATIONS FOR ALL FINISHES.

4. PROVIDE AFFIDAVITS FOR ALL FINISH MATERIALS TO VERIFY FLAME SPREAD AND SMOKE DEVELOPMENT IN ACCORDANCE WITH NFPA.

5. TRADE CONTRACTOR TO PREPARE ALL EXISTING SURFACES FOR NEW FINISH - INCLUDING INFILL OF FLOOR IMPERFECTIONS AND FLOOR LEVELING.

6. INSTALL TRANSITION STRIP OR TERMINATION EDGE BETWEEN ALL DISSIMILAR FLOORING MATERIALS. REFER TO FLOOR FINISH PLANS AND LEGEND. LOCATE UNDER DOOR WHERE TRANSITION HAPPENS BETWEEN ENCLOSED ROOMS.


7. TRADE CONTRACTOR TO PROVIDE A MINIMUM QUANTITY OF 5% OVERAGE (IN ADDITION TO THE AMOUNT DETERMINED FOR INSTALLATION PURPOSES) OF EACH FLOOR MATERIAL SPECIFIED FOR THIS PROJECT FOR THE OWNER'S USE AFTER COMPLETION OF THE PROJECT.


8. TRADE CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND DISPOSAL OF EXISTING FLOOR MATERIALS AND FOR FOLLOWING MANUFACTURER RECOMMENDED FLOOR PREP FOR A PROPER, SMOOTH AND LEVEL INSTALLATION OF THE NEW FLOOR MATERIALS IN ITS PLACE. NO EXCEPTIONS A FIELD VISIT IS REQUIRED TO ASSESS CURRENT CONDITIONS.

9. THE GENERAL CONTRACTOR AND THE SUBCONTRACTOR(S) RESPONSIBLE FOR SUPPLY AND INSTALLATION OF THESE FINISH MATERIALS ARE RESPONSIBLE FOR VERIFYING THE LEAD TIME AND FOR ROBETING/RECEIVING THE MATERIAL TO INSURE AN INSTALLATION DATE THAT DOES NOT DELAY CONSTRUCTION SCHEDULE. THESE MATERIALS HAVE BEEN REVIEWED AND APPROVED BY THE OWNER. NO SUBSTITUTIONS WILL BE ACCEPTED DUE TO UNTIMELY ORDER ENTRY/RECEIPT


10. DIMENSIONS SHOWN ARE FOR REFERENCE, VERIFY ALL DIMENSIONS IN

11. CLEAN ALL EXISTING FLOORS TO REMAIN EXCEPT AREAS SPECIFICALLY NOTED AS OUT OF SCOPE.





KEY PLAN





GRPS my choice

GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION

25.102

FIRST FLOOR PLAN - PART B

A101b



FINISH SCHEDULE

CORNERSTONE ARCHITECTS **GRPS** GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION Date Issued For 12.14.2025 SD PROGRESS 02.28.2025 SCHEMATIC DESIGN 03.18.2025 BIDS & PERMITS

25.102

SECOND FLOOR PLAN - PART A

A102a

PART A

PART B

SECOND FLOOR - PART A



7,488.0 SQ FT

IISH SCHEDULE

YPE PRODUCT MANUFACTURER STYLE COLOR SIZE REMARKS

3,882.0 SQ FT

3,882.0 SQ FT

199.1 SQ FT

199.1 SQ FT

199.1 SQ FT

293.3 FT

1,054.2 FT

86.1 FT

WITH RESTORATION TO "LIKE NEW" CONDITIONS OF ALL DAMAGED SURFACES AND ITEMS.

2. ALL FASTENINGS AND ATTACHMENTS OF LIKE AND DIFFERENT MATERIALS SHALL BE FULLY CONCEALED FROM VIEW.

3.ALL MATERIAL FINISH SELECTIONS (COLORS, MANUFACTURERS, PATTERNS, ETC.) TO BE DETERMINED BY ARCHITECT AND APPROVED BY BUILDING OWNER. SAMPLES OF ALL FINISHES SHALL BE SUBMITTED TO THE ARCHITECT OR APPROVAL PRIOR TO ORDERING AND INSTALLING. SHOP DRAWINGS SHALL INCLUDE LOCATIONS FOR ALL FINISHES.

4. PROVIDE AFFIDAVITS FOR ALL FINISH MATERIALS TO VERIFY FLAME SPREAD AND SMOKE DEVELOPMENT IN ACCORDANCE WITH NFPA.

5. TRADE CONTRACTOR TO PREPARE ALL EXISTING SURFACES FOR NEW FINISH - INCLUDING INFILL OF FLOOR IMPERFECTIONS AND FLOOR LEVELING.

6. INSTALL TRANSITION STRIP OR TERMINATION EDGE BETWEEN ALL DISSIMILAF FLOORING MATERIALS. REFER TO FLOOR FINISH PLANS AND LEGEND. LOCATE UNDER DOOR WHERE TRANSITION HAPPENS BETWEEN ENCLOSED ROOMS.


7. TRADE CONTRACTOR TO PROVIDE A MINIMUM QUANTITY OF 5% OVERAGE (IN ADDITION TO THE AMOUNT DETERMINED FOR INSTALLATION PURPOSES) OF EACH FLOOR MATERIAL SPECIFIED FOR THIS PROJECT FOR THE OWNER'S USE AFTER COMPLETION OF THE PROJECT.


8. TRADE CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND DISPOSAL OF EXISTING FLOOR MATERIALS AND FOR FOLLOWING MANUFACTURER RECOMMENDED FLOOR PREP FOR A PROPER, SMOOTH AND LEVEL INSTALLATION OF THE NEW FLOOR MATERIALS IN ITS PLACE. NO EXCEPTIONS A FIELD VISIT IS REQUIRED TO ASSESS CURRENT CONDITIONS.

9. THE GENERAL CONTRACTOR AND THE SUBCONTRACTOR(S) RESPONSIBLE FOR SUPPLY AND INSTALLATION OF THESE FINISH MATERIALS ARE RESPONSIBLE FOR VERIFYING THE LEAD TIME AND FOR ORDERING/RECEIVING THE MATERIAL TO INSURE AN INSTALLATION DATE THAT DOES NOT DELAY CONSTRUCTION SCHEDULE. THESE MATERIALS HAVE BEEN REVIEWED AND APPROVED BY THE OWNER. NO SUBSTITUTIONS WILL BE ACCEPTED DUE TO UNTIMELY ORDER ENTRY/RECEIPT

10. DIMENSIONS SHOWN ARE FOR REFERENCE, VERIFY ALL DIMENSIONS IN

11. CLEAN ALL EXISTING FLOORS TO REMAIN EXCEPT AREAS SPECIFICALLY NOTED AS OUT OF SCOPE.





KEY PLAN



SECOND FLOOR - PART B



CORNERSTONE
ARCHITECTS
1225, Union, 5to, 200 440, Bridge 51, Mills
1231, 947, 2177 618, 774, 2010 0
www.comerstone-orch.com

GRPS my chice


GESAR E CHAVEZ
ELEMENTARY SCHOOL RENOVATION

Date Issued For
02.14.2025 SD PROGRESS
02.28.2025 DESIGN
03.18.2025 BIDS & PERMITS

PIC: T. Nemit
PM: A. Dance
PROJECT NO:
25.102

SECOND FLOOR PLAN - PART B

A102b



CORNERSTONE
ARCHITECTS
122 S. Union, 51e, 200
123 S. Union, 51e, 200
123 S. Union, 51e, 200
1240 Region, 51e, 100
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2117)
12194 (2

GRAND RAPIDS PUBLIC SCHOOLS

CESAR E CHAVEZ

ELEMENTARY SCHOOL RENOVATION

| Date | Issued For | 02.14.2025 | SD PROGRESS | SCHEMATIC | DESIGN | 03.18.2025 | BIDS & PERMITS | BIDS & BIDS & PERMITS | BIDS & BIDS & PERMITS | BIDS & PERM

THIRD FLOOR PLAN - PART A

A103a

FINISH SCHEDULE TYPE PRODUCT MANUFACTURER STYLE COLOR SIZE REMARKS BASE FLOOR CPT-1 CARPET TILE TRANSITION STRIPS TS-1 TRANSITION STRIPS TS-1 TRANSITION STRIPS TS-1 TRANSITION STRIPS TS-1 TRANSITION STRIPS TARKE B1 TOLOR TRANSITION STRIPS TARKE TRANSITION STRIPS TARKE TOLOR TRANSITION STRIPS TARKE TARKE TARKE TOLOR TOLOR

GENERAL FINISH NOTES

1. PROJECT CLEAN UP SHALL INCLUDE A "VACUUM CLEAN" INTERIOR SPACE WITH RESTORATION TO "LIKE NEW" CONDITIONS OF ALL DAMAGED SURFACES AND ITEMS.

PART A

 $2.\mbox{ALL}$ FASTENINGS AND ATTACHMENTS OF LIKE AND DIFFERENT MATERIALS SHALL BE FULLY CONCEALED FROM VIEW.

3.ALL MATERIAL FINISH SELECTIONS (COLORS, MANUFACTURERS, PATTERNS, ETC.) TO BE DETERMINED BY ARCHITECT AND APPROVED BY BUILDING OWNER. SAMPLES OF ALL FINISHES SHALL BE SUBMITTED TO THE ARCHITECT OR APPROVAL PRIOR TO ORDERING AND INSTALLING. SHOP DRAWINGS SHALL INCLUDE LOCATIONS FOR ALL FINISHES.

 $4.\mbox{PROVIDE}$ AFFIDAVITS FOR ALL FINISH MATERIALS TO VERIFY FLAME SPREAD AND SMOKE DEVELOPMENT IN ACCORDANCE WITH NFPA.

5. TRADE CONTRACTOR TO PREPARE ALL EXISTING SURFACES FOR NEW FINISH - INCLUDING INFILL OF FLOOR IMPERFECTIONS AND FLOOR LEVELING.

6.INSTALL TRANSITION STRIP OR TERMINATION EDGE BETWEEN ALL DISSIMILAF FLOORING MATERIALS. REFER TO FLOOR FINISH PLANS AND LEGEND. LOCATE UNDER DOOR WHERE TRANSITION HAPPENS BETWEEN ENCLOSED ROOMS.


7. TRADE CONTRACTOR TO PROVIDE A MINIMUM QUANTITY OF 5% OVERAGE (IN ADDITION TO THE AMOUNT DETERMINED FOR INSTALLATION PURPOSES) OF EACH FLOOR MATERIAL SPECIFIED FOR THIS PROJECT FOR THE OWNER'S USE AFTER COMPLETION OF THE PROJECT.


8. TRADE CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND DISPOSAL OF EXISTING FLOOR MATERIALS AND FOR FOLLOWING MANUFACTURER RECOMMENDED FLOOR PREP FOR A PROPER, SMOOTH AND LEVEL INSTALLATION OF THE NEW FLOOR MATERIALS IN IT'S PLACE. NO EXCEPTIONS A FIELD VISIT IS REQUIRED TO ASSESS CURRENT CONDITIONS.

9. THE GENERAL CONTRACTOR AND THE SUBCONTRACTOR(S) RESPONSIBLE FOR SUPPLY AND INSTALLATION OF THESE FINISH MATERIALS ARE RESPONSIBLE FOR VERIFYING THE LEAD TIME AND FOR ORDERING/RECEIVING THE MATERIAL TO INSURE AN INSTALLATION DATE THAT DOES NOT DELAY CONSTRUCTION SCHEDULE. THESE MATERIALS HAVE BEEN REVIEWED AND APPROVED BY THE OWNER. NO SUBSTITUTIONS WILL BE ACCEPTED DUE TO UNTIMELY ORDER ENTRY/RECEIPT

10. DIMENSIONS SHOWN ARE FOR REFERENCE, VERIFY ALL DIMENSIONS IN


11. CLEAN ALL EXISTING FLOORS TO REMAIN EXCEPT AREAS SPECIFICALLY NOTED AS OUT OF SCOPE.





KEY PLAN





CORNERSTONE ARCHITECTS 1223- Union, Ste. 200 440 Bridge St. NW Browner St. 200 440 Bridge St. NW 2013-W. 2017 M. ACCOUNTS AND ACCOUNTS

GRPS my choice

GESAR E CHAVEZ
ELEMENTARY SCHOOL RENOVATION

Date Issued For 02.14.2025 SPROGRESS CO.2.28.2025 SCHEMATIC DESIGN CO.3.18.2025 BIDS & PERMITS

PIC: T. Nemitz PM: A. Dancer PROJECT NO: 25.102

SHEET TITLE: THIRD FLOOR PLAN - PART B

A103b